

**PROJECT NO. 38-CW-1(SG)**  
**LAUDERDALE COUNTY BID NO. 3843**  
**SITE GRADING AT THE 1-20/59 INDUSTRIAL PARK**  
**LAUDERDALE COUNTY**

**ADDENDUM NO. 5**

TO: ALL BIDDERS ON THE ABOVE REFERENCED PROJECT

FROM: Terrell W. Temple, P.E.

DATE: January 7, 2019

SUBJECT: ADDENDUM NO. 5

- I. Replace Section 902, Proposal Sheet, previously submitted and instead, use the attached Section 902, Proposal Sheet.
  - A. This addendum increases quantities of materials to be used for erosion control.
  - B. This addendum deletes relocation of gas lines. Instead, the gas lines will be relocated by Atmos at no cost to the contractor.

Submitted By:



\_\_\_\_\_  
Project Engineer

\_\_\_\_\_  
Contractor

\_\_\_\_\_  
January 7, 2019

Date

\_\_\_\_\_  
Date

**THIS ADDENDUM SHALL BE SIGNED, DATED AND SUBMITTED WITH BID DOCUMENTS.**

**FAILURE TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM AND ATTACH IT TO CONTRACT DOCUMENTS SHALL BE GROUNDS FOR REJECTING PROPOSAL.**

SITE GRADING AT MERIDIAN I-20/59 INDUSTRIAL PARK

I (We) agree to complete the entire project within 240 Calendar Days.

\*\*\*SPECIAL NOTICE TO BIDDERS\*\*\*

BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED

Ref. No.	Pay Item No.	Description	Approx. Quantity	Unit	Unit Price		Item Total	
					Dollars	Cents	Dollars	Cents
<b>SITE GRADING ITEMS</b>								
1	S-200-A	MOBILIZATION	1.00	LS	XXXXXXXXXXXXXX	XXXXXXXXXXXXXX		
2	S-201-A	CLEARING AND GRUBBING	1.00	LS	XXXXXXXXXXXXXX	XXXXXXXXXXXXXX		
3	S-202-B	REMOVAL AND SALVAGE OF FIRE HYDRANT	2.000	EA				
4	S-202-D	REMOVAL OF PAVEMENTS (ALL TYPES) (ALL DEPTHS)	3,644.00	SY				
5	S-203-A	UNCLASSIFIED EXCAVATION (FM)	1,869,771.00	CY				
6	S-211-A	TOPSOIL FOR SLOPE TREATMENT (8 INCH DEPTH)	189,000.00	SY				
<b>EROSION CONTROL ITEMS</b>								
7	901-S-212-A	AGRICULTURAL LIMESTONE	542.00	TON				
8	S-212-A	COMMERCIAL FERTILIZER (13-13-13)	271.00	TON				
9	S-212-F	AMMONIUM NITRATE	41.00	TON				
10	S-214-A	SEEDING	271.00	ACRE				
11	S-215-A	VEGETATIVE MATERIALS FOR MULCH	542.00	TON				
12	S-229-A	PORTLAND CEMENT CONCRETE PAVED DITCH	72.00	CY				
13	S-233-A	TEMPORARY SILT FENCE (TYPE ID)(AOS 0.15-0.84)	7,500.00	LF				
14	907-237-A	WATTLES, 20"	2,000.00	LF				
15	S-304-C	CRUSHED STONE (SIZE 24)(FOR CONSTRUCTION ENTRANC	500.00	TONS				
16	S-815-A	LOOSE RIPRAP, 100 LB	600.00	TON				
18	S-815-E	GEOTEXTILE UNDER RIPRAP/STONE (TYPE V)(AOS 0.21-0.41	500.00	SY				
18	901-S-236-A	DETENTION BASIN OUTLET STRUCTURE W/ SKIMMER	1.00	EA				
<b>TRAFFIC CONTROL ITEMS</b>								
19	S-618-A	MAINTENANCE OF TRAFFIC	1.000	LS	XXXXXXXXXXXXXX	XXXXXXXXXXXXXX		
20	S-618-B	ADDITIONAL CONSTRUCTION SIGNS	0.000	SF		10.00		
<b>UTILITY ITEMS</b>								
21	S-613-D	ADJUSTMENT OF SANITARY SEWER MANHOLE	3.00	EA				
22	S-613-D	ADJUSTMENT OF EXISTING FIRE HYDRANT	2.000	EA				
23	S-613-D	ADJUSTMENT OF EXISTING WATER VALVE	2.000	EA				
							<b>TOTAL BID</b>	