

**CONCESSION AND RESTROOM FACILITY  
KEMPER COUNTY – DeKALB PARK  
DeKALB, MS**

**ADDENDUM NO. 1**


TO: ALL PLAN HOLDERS ON THE ABOVE REFERENCED PROJECT  
FROM: Terrell W. Temple, P.E.  
DATE: March 18, 2020  
SUBJECT: **ADDENDUM NO. 1**

Clarifications and revisions to Contract Documents and Plans for the referenced project are as follow:

**NOTES FOR CLARIFICATION –**

1. Electrical components to be surface mounted. This includes wall switches, convenience outlets and conduit. Do not install within the block cores.
2. Toilet doors shall be plastic laminate as noted on sheet 7.0. Delete any reference to ‘solid plastic’ doors. Doors shall be mounted on 4” block partition walls.
3. 4” block partition walls in the restrooms to be approximately 80” high. Construct to nearest complete block height. Top course of block to be solid concrete block.
4. Wood trusses may be constructed with a cantilevered overhang in lieu of construction as shown.
5. **ADD** – Masonry wire reinforcement (Dur-a-wall or similar) required in every other course for all CMU walls, both 8” and 4”.
6. **DELETE** – Delete the installation of #4 dowels as shown in detail 3 sheet 3.0. All other requirements remain the same.

Submitted By:



Terrell W. Temple, P.E.  
County Engineer

3/18/20

Date

Acknowledged by:

\_\_\_\_\_  
Contractor’s signature

\_\_\_\_\_  
Company

\_\_\_\_\_  
Date

ADDENDUM SHALL BE ACKNOWLEDGED BY CONTRACTOR AND INCLUDED IN BID PACKAGE.  
FAILURE TO INCLUDE ACKNOWLEDGEMENT MAY BE GROUNDS FOR REJECTION.