

**DEKALB LAGOON IMPROVEMENTS
TOWN OF DEKALB
KEMPER COUNTY, MISSISSIPPI**

ADDENDUM NO. 1

TO: ALL BIDDERS ON THE ABOVE REFERENCED PROJECT
FROM: Richmond L. Alexander, P.E.
DATE: November 9, 2016
SUBJECT: **ADDENDUM NO. 1**

Clarifications and Modifications to contract documents issued for the referenced project include the following:

1. Bid Sheet:

Replace Bid Sheet with attached Bid Sheet dated 11-9-16.

Clarification No. 1:


Alternate No. 1 shall consist of material only.

Clarification No. 2:

Alternate No. 2 shall be the excavation, disposal and replacement of the sand media in the existing sand filters (2 cells). The existing sand media that is excavated shall be disposed of in a Municipal Solid Waste Landfill. The Contractor is responsible for all disposal fees associated with the disposal of sand media.

Alternate No. 3 shall be the excavation, disposal and replacement of the sand media in the existing sand filters (2 cells). The existing sand media that is excavated shall be disposed of in the *out of service sand filter* location on-site.

Submitted By:



Project Engineer

11/9/16

Date

Acknowledged By:

Contractor

Date

THIS ADDENDUM SHALL BE SIGNED, DATED AND SUBMITTED WITH BID DOCUMENTS. FAILURE TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM AND ATTACH IT TO CONTRACT DOCUMENTS SHALL BE GROUNDS FOR REJECTING PROPOSAL.

****SPECIAL NOTICE TO BIDDERS**
BIDS WILL NOT BE CONSIDERED UNLESS BOTH UNIT PRICES AND ITEM TOTALS ARE ENTERED**

ITEM NO.	ITEM DESCRIPTION	UNIT	ESTIMATED QUANTITY	UNIT PRICE	TOTAL AMOUNT
DEKALB LAGOON IMPROVEMENTS - BASE BID					
1	Mobilization	L.S.	1		
2	Lagoon Master Water Moving Aerator	EA	2		
3	8" PVC (SDR-26) Gravity Sewer Line	L.F.	345		
4	New 8" Gate Valve (including box)	EA	1		
5	48" Precast Sewer Manhole (0'-6" depth)	EA	1		
6	Structural Concrete (including steel reinforcement)	C.Y.	10		
7	Tie to Existing Structures	L.S.	1		
8	New Sand Filter Sprinkler Nozzels	EA	12		
9	Size No. 67 Stone Base	C.Y.	25		
10	Grassing (Erosion & Stormwater Control Measures)	L.S.	1		
DEKALB LAGOON IMPROVEMENTS - ADDITIVE ALTERNATE NO. 1					
11	Lagoon Master Water Moving Aerator (Back-up)	EA	1		
DEKALB LAGOON IMPROVEMENTS - ADDITIVE ALTERNATE NO. 2					
12	Unclassified Excavation, FM (Sand Filters), Disposal at Municipal Landfill	C.Y.	2,100		
13	Borrow Excavation, FM (Filter Sand)	C.Y.	2,700		
DEKALB LAGOON IMPROVEMENTS - ADDITIVE ALTERNATE NO. 3					
14	Unclassified Excavation, FM (Sand Filters), Temporary Disposal on-site	C.Y.	2,100		
15	Borrow Excavation, FM (Filter Sand)	C.Y.	2,700		

TOTAL BID: _____

Contractor: _____

By: _____

Address: _____

Date: _____