

**FACILITY ADDITION FOR
EMILIA RESOURCES
ARC GRANT NO. MS-19249-2018
KEMPER COUNTY BOARD OF SUPERVISORS
KEMPER COUNTY, MISSISSIPPI**

ADDENDUM NO. 5

TO: ALL BIDDERS ON THE ABOVE REFERENCED PROJECT


FROM: Terrell W. Temple, P.E.

DATE: January 9, 2019

SUBJECT: ADDENDUM NO. 5

1. **CLARIFICATION:** Specification Section 16620 – Paging system is not included in the contract.
2. **CLARIFICATION:** Refer to Sheet A6.0 – The telephone backboard shall be mounted on the North wall of Electrical Room 110.
3. **CLARIFICATION:** Service conduit for communications shall be 2 – 3” dia.
4. **GENERAL INFORMATION:** Design conditions for the ARUs: Outdoor temperature (DB) 96°F; Indoor temperature 78°F @ 60-65% humidity
5. **GENERAL INFORMATION:** Considerations used for design purposes are as follows:
Racking (final selection of racking system will be by others N.I.C.): Racking (provided by others) will be steel units; max. 6 units high for a max. material storage height of ±30’0”AFF; max. shelf height ±26’0”; slatted shelving.
Materials to be stored in the new building will be encapsulated.

Submitted By:



Project Engineer

Contractor

January 9, 2019

Date

Date

THIS ADDENDUM SHALL BE SIGNED, DATED AND SUBMITTED WITH BID DOCUMENTS.

FAILURE TO ACKNOWLEDGE RECEIPT OF THIS ADDENDUM AND ATTACH IT TO CONTRACT DOCUMENTS SHALL BE GROUNDS FOR REJECTING PROPOSAL.