

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, DeKalb, Mississippi, until 10:00 am on the 6th day of March, 2017 and shortly thereafter publicly opened for the construction of 0.108 miles of PRECAST CONCRETE SPAN BRIDGE & GRAVEL SURFACE APPROACHES on the BEALMAN being known as Project No. LSBP-35(17) in Kemper County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
<u>ROADWAY ITEMS:</u>		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STA. 13+03	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	656.000	CY
BORROW EXCAVATION (F.M.E.)	246.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GRANULAR MATERIAL (LVM),	429.000	CY
(CLASS 9, GROUP B)		
SIZE (I) STABILIZER AGGREGATE,	58.000	CY
COARSE		
RIGHT-OF-WAY MARKERS (TYPE II)	10.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
REFLECTORIZED TRAFFIC OBJECT MARKER	4.000	EA
(ENCAPSULATED LENS) (TYPE 3)		
<u>EROSION CONTROL ITEMS:</u>		
AGRICULTURAL LIMESTONE	1.500	TON
COMMERCIAL FERTILIZER (13-13-13)	0.750	TON
SEEDING	0.750	AC
VEGETATIVE MATERIALS FOR MULCH	1.500	TON
SOLID SODDING	100.000	SY
TEMPORARY SILT FENCE	1,070.000	LF
(TYPE II) (AOS 0.15-0.84)		
LOOSE RIPRAP, 200 LB.	40.000	TON
WATTLES, 20"	200.000	LF
<u>BRIDGE ITEMS:</u>		
TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	920.000	LF

SECTION 900
 PROJECT NO. LSBP-35(17)
 KEMPER COUNTY

18" PRE-FORMED PILE HOLES	714.000	LF
31' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	24.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
31' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	8.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	328.000	LF
31.00' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE,	2.000	EA
31.00' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE,	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	85.000	TON
GEOTEXTILE UNDER 300 LB. RIPRAP, TYPE V, AOS 0.21-0.43	158.000	SY

PROJECT NO. LSBP-35(17)
KEMPER COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 120 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County, the LSBP Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, LSBP Engineer for Kemper County, Mississippi, 1724B 23RD Avenue, Meridian. The Cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Johnny Whitsett, President
Kemper County Board of Supervisors