

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
LAUDERDALE COUNTY BOARD OF SUPERVISORS

SECTION 900-A

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Lauderdale County, Mississippi at the Lauderdale County Courthouse Annex, Meridian, Mississippi, until 10:00 a.m. on the 13th day of August, 2019 and shortly thereafter publicly opened for the construction of 0.146 miles of PRECAST CONCRETE BRIDGE & HMA APPROACHES on the WOODS ROAD being known as Project No. ERBR-SAP-38(95) in Lauderdale County, Mississippi. Contractors have the option of submitting bids either electronically by Central Bidding, www.centralbidding.com or paper sealed bids addressed and delivered to the Lauderdale County Board of Supervisors, at the time and date noted above.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

ITEM	QUANTITY	UNIT
ROADWAY ITEMS:		
MOBILIZATION	LUMP SUM	LS
CLEARING AND GRUBBING	LUMP SUM	LS
REMOVAL OF BRIDGE AT STA. 158+56.42	1.000	UN
UNCLASSIFIED EXCAVATION (FM)	1,124.000	CY
BORROW EXCAVATION (F.M.E.)	780.000	CY
(CONTRACTOR FURNISHED) (CLASS 9)		
GRANULAR MATERIAL (LVM),	749.000	CY
(CLASS 9, GROUP B)		
SIZE I STABILIZER AGGREGATE,	12.000	CY
COARSE		
HOT MIX ASPHALT BASE COARSE, (BB-1)	358.000	TON
HOT BITUMINOUS PAVEMENT SURFACE	135.000	TON
COARSE, (SC-1), (TYPE 8)		
CLASS "B" STRUCTURAL CONCRETE,	0.580	CY
MINOR STRUCTURES		
15" REINFORCED CONCRETE PIPE,	96.000	LF
CLASS III		
48" REINFORCED CONCRETE PIPE,	64.000	LF
CLASS III		
48" REINFORCED CONCRETE PIPE,	4.000	EA
END SECTION		
29" X 18" REINFORCED CONCRETE	32.000	LF
ARCH PIPE, CLASS III		
29" X 18" REINFORCED CONCRETE	2.000	EA
ARCH PIPE, END SECTION		
GUARD RAIL, W-BEAM	50.000	LF
GUARD RAIL, BRIDGE END SECTION,	4.000	EA
TYPE "I" THRIE-BEAM		
GUARD RAIL, TERMINAL END SECTION	4.000	EA
RIGHT-OF-WAY MARKERS (TYPE II)	21.000	EA
MAINTENANCE OF TRAFFIC	LUMP SUM	LS
ADDITIONAL CONSTRUCTION SIGNS	0.000	SF
4" WIDE THERMOPLASTIC TRAFFIC	1,550.000	LF
STRIPE (CONTINUOUS YELLOW) (120 MIL)		

SECTION 900-A
 PROJECT NO. ERBR-SAP-38(95)
 LAUDERDALE COUNTY

TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS	20.000	EA
REFLECTORIZED TRAFFIC WARNING SIGN (ENCAPSULATED LENS)	2.000	EA
REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3)	4.000	EA
REFLECTORIZED TRAFFIC DELINEATOR SIGN (ENCAPSULATED LENS)	14.000	EA

EROSION CONTROL ITEMS:

AGRICULTURAL LIMESTONE	3.040	TON
COMMERCIAL FERTILIZER (13:13:13)	1.520	TON
AMMONIUM NITRATE	0.230	TON
SEEDING	1.520	AC
VEGETATIVE MATERIALS FOR MULCH	3.040	TON
SOLID SODDING	500.000	SY
TEMPORARY SILT FENCE (TYPE II) (A.O.S. 0.15-0.84)	2,100.000	LF
WATTLES, 20"	500.000	LF
LOOSE RIPRAP, 200 LB.	60.000	TON

BRIDGE ITEMS:

TEST PILE	2.000	EA
CONVENTIONAL STATIC PILE LOAD TEST	0.000	EA
14" PRESTRESSED CONCRETE PILING	600.000	LF
18" PRE-FORMED PILE HOLES	392.000	LF
19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	12.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR	6.000	EA
19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	4.000	EA
40' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR	2.000	EA
PRECAST CONCRETE BARRIER RAIL	156.000	LF
31.33' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE	2.000	EA
31.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE	2.000	EA
9.25' PRECAST CONCRETE WING	4.000	EA
LOOSE RIPRAP, 300 LB.	150.000	TON
GEOTEXTILE UNDER RIPRAP, TYPE V, AOS 0.21-0.43	376.000	SY

PROJECT NO. ERBR-SAP-38(95)
LAUDERDALE COUNTY

NOTICE TO CONTRACTORS:

CONTRACT TIME: 45 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Lauderdale County and the County Engineer's office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction. However, State Aid is not involved in this project.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, County Engineer for Lauderdale County, Mississippi, 1724B 23RD Avenue, Meridian. The Cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable or download from Central Bidding at www.centralbidding.com. Electronic bids can be submitted at www.centralbidding.com. For any questions relating to the electronic bidding process, please call Central Bidding at 225-810-4814.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Lauderdale County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Jonathan Wells, President
Lauderdale County Board of Supervisors