

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
SMITH COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Smith County, Mississippi at the Smith County Courthouse, Raleigh, Mississippi, until 10:00 am on the 11th day of December, 2018 and shortly thereafter publicly opened for the construction of 0.136 miles of DBL BOX BRIDGE & GRAVEL SURFACE APPROACHES on the TRENTON-LORENA ROAD being known as Project No. SAP-65(64) in Smith County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| ITEM | QUANTITY | UNIT |
|--|-----------|------|
| <u>ROADWAY ITEMS:</u> | | |
| MOBILIZATION | LUMP SUM | LS |
| CLEARING AND GRUBBING | LUMP SUM | LS |
| REMOVAL OF BRIDGE AT STA. 12+08.69 | 1.000 | UN |
| UNCLASSIFIED EXCAVATION (FM) | 812.000 | CY |
| BORROW EXCAVATION (F.M.E.) (CONTRACTOR FURNISHED) (CLASS 9) | 1,403.000 | CY |
| CHANNEL EXCAVATION (FM) | 28.000 | CY |
| EXCESS EXCAVATION (FM) | 305.000 | CY |
| TEMPORARY STREAM DIVERSION | 1.000 | EA |
| GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B) | 1,310.000 | CY |
| SIZE I STABILIZER AGGREGATE, COARSE | 212.000 | CY |
| MIXING, SHAPING AND COMPACTION | 1,772.000 | SY |
| 15" REINFORCED CONCRETE PIPE, CLASS III | 32.000 | LF |
| 18" REINFORCED CONCRETE PIPE, CLASS III | 64.000 | LF |
| FILTER MATERIAL FOR FILTER BEDS, TYPE I | 458.000 | CY |
| RIGHT-OF-WAY MARKERS (TYPE I) | 21.000 | EA |
| MAINTENANCE OF TRAFFIC | LUMP SUM | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.000 | SF |
| <u>EROSION CONTROL ITEMS:</u> | | |
| AGRICULTURAL LIMESTONE | 1.740 | TON |
| COMMERCIAL FERTILIZER (13:13:13) | 0.870 | TON |
| AMMONIUM NITRATE | 0.130 | TON |
| SEEDING | 0.870 | AC |
| VEGETATIVE MATERIALS FOR MULCH | 2.610 | TON |
| SOLID SODDING | 120.000 | SY |
| TEMPORARY SILT FENCE | 1,362.000 | LF |

SECTION 900
PROJECT NO. SAP-65(64)
SMITH COUNTY

(TYPE II) (AOS 0.15-0.84)
WATTLES, 20"
LOOSE RIPRAP, 200 LB.
LOOSE RIPRAP, 300 LB.

| | |
|---------|-----|
| 800.000 | LF |
| 100.000 | TON |
| 19.000 | TON |

BOX BRIDGE ITEMS:

BOX BRIDGE CONCRETE, CLASS "BB"
REINFORCEMENT

| | |
|------------|----|
| 336.000 | CY |
| 63,609.000 | LB |

NOTICE TO CONTRACTORS:

CONTRACT TIME: 65 Working Days

BASIS OF AWARD

The award, if made, will be made to the lowest qualified bidder on the basis of published quantities.

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color, or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Smith County, the County Engineer's office and the Office of the State Aid Engineer, 412 E. Woodrow Wilson Avenue, Jackson, Mississippi. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, County Engineer for Smith County, Mississippi, 1724B 23rd Avenue, Meridian. The Cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable

Certified check or bid bond for five percent (5%) of the total bid, made payable to Smith County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

Howard Hammons, President
Smith County Board of Supervisors