

KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, DeKalb, Mississippi, until 10:00 a.m. on the 14th day of January, 2021 and shortly thereafter publicly opened for the replacement of a deficient bridge with a new structure and approaches – 3@19’ on the Sunflower Road being known as Project No. ERBR-35(01) in Kemper County, Mississippi.

CONTRACT TIME: 60 Working Days

BASIS OF AWARD:

The Board of Supervisors hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of race, color or national origin in consideration for an award.

PLANS AND SPECIFICATIONS are on file in the Office of the Chancery Clerk of Kemper County and the County Engineer’s office. This project shall be constructed in accordance with the latest edition of the Mississippi Standard Specifications for State Aid Road and Bridge Construction.

PLANS AND PROPOSALS may be secured from Terrell W. Temple, Engineer for Kemper County, Mississippi, 1724B 23rd Avenue, Meridian, MS 39301. The cost is twenty-five dollars (\$25.00) for plans and twenty-five dollars (\$25.00) for the proposal, non-refundable.

Certified check or bid bond for five percent (5%) of the total bid, made payable to Kemper County and the State of Mississippi must accompany each proposal.

Bidders are hereby notified that any proposal accompanied by letters qualifying in any manner the condition under which the proposal is tendered will be considered an irregular bid and such proposal will not be considered in making the award.

/s/ James “Pat” Granger, President
Kemper County Board of Supervisors

Advert. December 10, 2020
December 17, 2020

OFFICE OF STATE AID ROAD CONSTRUCTION
MISSISSIPPI DEPARTMENT OF TRANSPORTATION
AND
KEMPER COUNTY BOARD OF SUPERVISORS

SECTION 900-A

NOTICE TO CONTRACTORS:

Sealed bids will be received by the Board of Supervisors of Kemper County, Mississippi at the Kemper County Courthouse, DeKalb, Mississippi, until 10:00 a.m. on the 14th day of January, 2021 and shortly thereafter publicly opened for the construction of 0.089 miles of replacement of a deficient bridge with a new structure and approaches and other incidental items on the Sunflower Road being known as Project No. ERBR-35(01) in Kemper County, Mississippi.

PRINCIPAL ITEMS OF WORK ARE APPROXIMATELY AS FOLLOWS:

| <u>ITEM</u> | <u>QUANTITY</u> | <u>UNIT</u> |
|--|-----------------|-------------|
| ROADWAY ITEMS: | | |
| MOBILIZATION | LUMP SUM | LS |
| CLEARING AND GRUBBING | LUMP SUM | LS |
| REMOVAL OF BRIDGE AT STA. 17+16.00 | 1.00 | UNIT |
| TRANSPORT OF BRIDGE AND GUARDRAIL COMPONENTS | LUMP SUM | LS |
| UNCLASSIFIED EXCAVATION (FM) | 103.00 | CY |
| BORROW EXCAVATION (FME)(CONTRACTOR FURNISHED)(CLASS 9) | 331.00 | CY |
| GRANULAR MATERIAL (LVM), (CLASS 9, GROUP B) | 186.00 | CY |
| SIZE I STABILIZER AGGREGATE, COARSE | 6.00 | CY |
| HOT BITUMINOUS PAVEMENT BASE COURSE (BB-1) | 26.00 | TON |
| HOT BITUMINOUS PAVEMENT SUFRACE COURSE (SC-1)(TYPE 8) | 109.00 | TON |
| 15" REINFORCED CONCRETE PIPE, CLASS III | 48.00 | LF |
| GUARDRAIL, W-BEAM | 75.00 | LF |
| GUARDRAIL, BRIDGE END SECTION, TYPE "I" THRIE-BEAM | 4.00 | EA |
| GUARDRAIL, TERMINAL END SECTION | 4.00 | EA |
| MAINTENANCE OF TRAFFIC | LUMP SUM | LS |
| ADDITIONAL CONSTRUCTION SIGNS | 0.00 | SF |
| 4" WIDE THERMOPLASTIC EDGE STRIPE (CONTINUOUS WHITE) (90 MIL) | 0.18 | MI |
| 4" WIDE THERMOPLASTIC TRAFFIC STRIPE (SKIP YELLOW) (120 MIL) | 0.09 | MI |
| TWO-WAY YELLOW REFLECTIVE HIGH PERFORMANCE RAISED MARKERS | 6.00 | EA |
| REFLECTORIZED TRAFFIC OBJECT MARKER (ENCAPSULATED LENS) (TYPE 3) | 4.00 | EA |

SECTION 900-A
 PROJECT NO. ERBR-35(01)
 KEMPER COUNTY

EROSION CONTROL ITEMS:

| | | |
|---|----------|------|
| AGRICULTURAL LIMESTONE | 1.38 | TON |
| COMMERCIAL FERTILIZER (13:13:13) | 0.69 | TON |
| AMMONIUM NITRATE | 0.15 | TON |
| SEEDING | 0.69 | ACRE |
| VEGETATIVE MATERIALS FOR MULCH | 2.07 | TON |
| SOLID SODDING | 50.00 | SY |
| TEMPORARY SILT FENCE (TYPE II) (AOS 0.15-0.84) | 1,000.00 | LF |
| WATTLES, 20" | 50.00 | LF |
| LOOSE RIPRAP, 200 LB | 50.00 | TON |
| GEOTEXTILE UNDER 200 LB. RIPRAP (TYPE V) (AOS 0.21-0.43) | 120.00 | SY |

BRIDGE ITEMS:

| | | |
|---|--------|-----|
| TEST PILES | 2.00 | EA |
| CONVENTIONAL STATIC PILE LOAD TEST | 0.00 | EA |
| 14" PRESTRESSED CONCRETE PILING | 520.00 | LF |
| 18" PRE-FORMED PILE HOLES | 460.00 | LF |
| 19' PRECAST CONCRETE SLAB UNIT, 3.5' INTERIOR | 18.00 | EA |
| 19' PRECAST CONCRETE SLAB UNIT, 3.5' EXTERIOR | 6.00 | EA |
| PRECAST CONCRETE BARRIER RAIL | 114.00 | LF |
| 31.0' PRECAST CONCRETE CAP, INTERMEDIATE UNIT, CONCRETE PILE | 2.00 | EA |
| 31.0' PRECAST CONCRETE CAP, END UNIT, CONCRETE PILE | 2.00 | EA |
| 9.25' PRECAST CONCRETE WING | 4.00 | EA |
| LOOSE RIPRAP, 300 LB | 187.00 | TON |
| GEOTEXTILE UNDER 300 LB RIPRAP (TYPE V) (AOS 0.21-0.43) | 478.00 | SY |